

Agenda





- Over a decade in the making
- EA/FONSI and 30%
 Design completed
 in 2014

Proposed Pedestrian Bridge



Beach Drive NW Reconstruction FHWA-EFLHD includes 1.4 miles of trail rehabilitation

> Proposed Retaining Wall Repair

- 2.4 miles of pavement rehabilitation /widening
- 1.2 miles of new trail connections
- Pedestrian Structure
- 11.4 Acre Limit of Disturbance

Zoo Loop




Project Overview



Stakeholders

- General Public
 - Park Visitors ~ 2 million/year
 - Commuters ~ 12 million/year
- Interest Groups
- Advisory Neighborhood Commissions
- Agency Stakeholders
 - National Park Service
 - Smithsonian Institution/National Zoological Park
 - US Park Police
 - US Secret Service
 - FHWA Eastern Federal Lands
 - DOEE, USACE, DC Water, PEPCO, WGL, CFA, SHPO

- Total length of work ~ 3.6 miles
- Rock Creek Park Multi-Use Trail from the Broad Branch/Grove 2 North parking area to P Street, NW;
- Piney Branch Trail from Beach Drive NW to Arkansas Avenue, NW - new 4,859-foot (0.9 mile) segment;
- Rose Park Trail –
 rehabilitation/widening of
 1,929-foot (0.4 mile) segment.
- Spans wards 1, 2, 3, & 4




Existing Trail

- Dense mix asphalt
- 6' to 7' wide

Proposed Trail

- Dense mix asphalt & porous asphalt
- Paved width: 8' to 10' wide
- Shoulders:
 - Crushed aggregate
 - 1' wide



Existing Trail Defects

Pavement deterioration







Ponding





Sediment build-up


Blocked culverts







Slope Failure

Existing and Proposed Rose Park Trail





Existing Trail, North of Lyons Mill Footbridge



Proposed Trail, North of Lyons Mill Footbridge



Existing Trail, North of Saddle Club Footbridge




Proposed Trail, North of Saddle Club Footbridge




Existing Trail, North of Porter Street NW




Proposed Trail, North of Porter Street NW




Existing Trail, South of Broad Branch Rd NW



Proposed Trail, South of Broad Branch Rd NW




Existing Trail, Piney Branch Trail at 16th Street NW



Proposed Trail, Piney Branch Trail at 16th Street NW



Klingle Valley Trail - Opened Sat. 6/24








- Precast concrete, single span, double-T section
- Two abutments on spread footings, stone facades
- Post & cable railing,
 54" height
- Deck lighting
- Designed to withstand major flooding




Pedestrian Bridge

- 10' Clear width
- 11-1/2' Out-to-Out
- 110' span




Section View



Flevation View from downstream

Elevation View



Deck View



Aerial Views





Abutment and Span Detail View



Project Overview: Additional Elements


- Drainage improvements
- Storm Water Management BMPs
- Piney Branch Retaining Wall repair
- Bank stabilization
- Landscape plantings
- Tree protection & removals
- Erosion and Sediment Control
- Lighting relocations and improvements
- Signing & Marking (including wayfinding)
- Fences





Detours and Closures


- Stages 0 7
- 21 24 month construction duration
- Proceed from south to north
- No lane closures in peak hours
- Avoid conflicts with Beach Drive NW reconstruction




- Mobilization
- Submittals
- Review and approvals
- Fabrication & Delivery of Materials
- 3 4 months



- Duration: 2-3 months
- Impacts to Motorists
 - Maintain one lane along P Street NW ramp; close ramp to traffic existing Rock Creek & Potomac Parkway SB;
 - Signed detour route: Penn. Ave NW, L Street NW, 22nd Ave NW
 - Unsigned detour route: RCPP to K Street NW, 29th Street NW




- Impacts to Bikes/Peds
 - Close Rose Park Trail
 - Signed detour route: RCPT to Pennsylvania Ave NW ramp
 - Unsigned detour routes available along neighborhood sidewalks to the west




- Duration: 4-6 months
- Impacts to Motorists
 - Rock Creek & Potomac Parkway: off-peak lane closures
- Impacts to Bikes/Peds
 - Close RCPT from P Street NW to Shoreham Dr NW
 - Signed detour route: Florida Ave NW, 19th St NW, Calvert St NW
 - Unsigned detour route:
 Through Dumbarton
 Oaks Park/Montrose Park




- Duration: 2-4 months
- Impacts to Motorists
 - Beach Drive NW: offpeak closures
 - Signed detour route:
 Tilden St NW,
 Connecticut Ave NW,
 Cathedral Ave NW
 - Detour is currently active for Beach Drive NW reconstruction project



- Impacts to Bikes/Peds
 - Close Zoo loop trail
 - Bikes/peds use tunnel sidewalk
 - During Beach Drive NW closures for ped bridge construction, bikes/peds to use roadway




- Duration: 2-4 months
- Impacts to Motorists: N/A
- Impacts to Bikes/Peds
 - Close Western Ridge Trail from Porter Street NW to Bluffs Footbridge
 - Use new trail along
 Beach Drive NW,
 currently under
 construction by EFLHD




- Duration: 4-6 months
- Impacts to Motorists
 - Close Piney Branch
 Parkway NW to WB traffic;
 maintain EB traffic
 - Signed detour route: 16th
 St NW, Park Rd NW, Klingle
 Rd NW, Porter St NW






- Impacts to Bikes/Peds
 - Close Piney Branch social trail
 - Signed detour route: 16th
 St NW, Park Rd NW,
 Klingle Rd NW, Porter St
 NW
 - Unsigned route available through woods south of parkway




- Duration: 2-3 months
- Impacts to Motorists: N/A
- Impacts to Bikes/Peds
 - Close RCPT from Grove 1 picnic area to Peirce Mill
 - Install temporary turfdecking trail; utilize
 Tilden Street NW raised crosswalk



- Turfdeck Temporary trail solution
- Stage 6 bypass route



- Duration: 1-2 months
- Impacts to Motorists: N/A
- Impacts to Bikes/Peds
 - Close social trail from Peirce Mill to Broad Branch Rd NW
 - Bikes/peds use existing trail from Peirce Mill to Grove 2 parking lot



- Duration: 1 month
- Impacts to Motorists: N/A
- Impacts to Bikes/Peds
 - Close existing trail from Peirce Mill to Grove 2 parking lot
 - Bikes/peds use new trail from Peirce Mill to Broad Branch Rd NW

