SS	EXISTING SANITARY SEWER MANHOLE
SD	EXISTING STORMDRAIN MANHOLE
CS	EXISTING COMBINED SANITARY & STORMDRAIN MANHOLE
W	EXISTING WATER MANHOLE
G T E	EXISTING GAS, TELEPHONE, ELECTRIC MANHOLE
M.H. ?	EXISTING MANHOLE - UNKNOWN
WM	EXISTING WATER METER
W	EXISTING WATER VALVE OR CUT-OFF
V SS	EXISTING SANITARY SEWER VENT
C.O.	EXISTING SANITARY SEWER CLEANOUT
GM	EXISTING GAS METER
G	EXISTING GAS VALVE OR CUT-OFF
V G	EXISTING GAS VENT
EM	EXISTING ELECTRIC METER
SS SD W	PROPOSED SANITARY SEWER, STORMDRAIN, WATER MANHOLE
	EXISTING FIRE HYDRANT
F	PROPOSED FIRE HYDRANT
WV GV	PROPOSED WATER VALVE, GATE VALVE
SIZE & TYPE	EXISTING CULVERT WITH DIRECTION OF FLOW
SIZE & TYPE	PROPOSED CULVERT WITH DIRECTION OF FLOW
U.D.	EXISTING UNDERDRAIN
U.D.	PROPOSED UNDERDRAIN

SIZE	EXISTING CATCH BASIN CONNECTION WITH DIRECTION OF FLOW
LENGTH & SIZE	PROPOSED CATCH BASIN CONNECTION WITH DIRECTION OF FLOW
SD	EXISTING SINGLE CATCH BASIN
SD SD	EXISTING DOUBLE CATCH BASIN
SD SD SD	EXISTING TRIPLE CATCH BASIN
SD	EXISTING SINGLE CATCH BASIN WITH DOUBLE THROAT ELONGATION
SD	EXISTING SINGLE CATCH BASIN WITH TRIPLE THROAT ELONGATION
	EXISTING SINGLE CATCH BASIN WITH GRATE
	EXISTING DOUBLE CATCH BASIN WITH GRATE
	PROPOSED SINGLE CATCH BASIN
	PROPOSED DOUBLE CATCH BASIN
	PROPOSED TRIPLE CATCH BASIN
	PROPOSED SINGLE CATCH BASIN WITH GRATE
	PROPOSED DOUBLE CATCH BASIN WITH GRATE
SIZE & TYPE SS CS SD W	EXISTING SANITARY SEWER, COMBINED SEWER, STORMDRAIN, WATER LINE LESS THAN 24"
SIZE & TYPE SS CS SD W	EXISTING SANITARY SEWER, COMBINED SEWER, STORMDRAIN, WATER LINE 24" OR GREATER
SIZE & TYPE G T E	EXISTING UNDERGROUND GAS, TELEPHONE, ELECTRIC LINE
SIZE & TYPE SS CS SD W	EXISTING SANITARY SEWER, COMBINED SEWER, STORMDRAIN, WATER LINE TO BE ABANDONED
SIZE & TYPE G T E	EXISTING UNDERGROUND GAS, TELEPHONE, ELECTRIC LINE TO BE ABANDONED
SIZE & TYPE SS CS SD W	EXISTING SANITARY SEWER, COMBINED SEWER, STORMDRAIN, WATER LINE TO BE REMOVED
SIZE & TYPE G T E	EXISTING UNDERGROUND GAS, TELEPHONE, ELECTRIC LINE TO BE REMOVED
LENGTH, SIZE & TYPE	PROPOSED STORMDRAIN LINE WITH DIRECTION OF FLOW, LESS THAN 24"
LENGTH, SIZE & TYPE	PROPOSED STORMDRAIN LINE WITH DIRECTION OF FLOW, 24" OR GREATER

P:\4035\DC Standard Drawings\Final\UNCHANGED\gen-01.dgn
Friday, April 03, 2009 AT 12:13 PM

DATE	APPR.	REFERENCE
REVISED		
ISSUED:		

RECOMMENDED: DEPUTY CHIEF ENGINEER

APPROVED: CHIEF TRANSPORTATION ENGINEER

STANDARD SYMBOLS

d. DISTRICT OF COLUMBIA
DEPARTMENT OF TRANSPORTATION

DWG. NO. GEN.01

	EXISTING RAILROAD
	EXISTING STREETCAR TRACKS
	PROPOSED LIMIT OF MAJOR WORK
	PROPOSED LIMIT OF REPAIR WORK
	EXISTING BUSH OR SHRUB
	EXISTING HEDGEROW
DIA. DIA.	EXISTING DECIDUOUS TREE, EVERGREEN TREE
	PROPOSED TREE
	EXISTING TREE STUMP
DIA.	EXISTING TREE TO BE REMOVED
DIA.	EXISTING TREE WITH TREE PROTECTION
HEIGHT	EXISTING WALL OR COPING
HEIGHT	PROPOSED WALL OR COPING
E.V.	EXISTING ELECTRIC VAULT
GUY	EXISTING GUY WIRE ANCHOR
	DIRECTION OF TRAFFIC
	EXISTING SIGN AND POST
	PROPOSED SIGN AND POST
M	EXISTING PARKING METER
F	EXISTING FIRE ALARM BOX
P	EXISTING POLICE CALL BOX
T	EXISTING TRASH/WASTE CAN
	EXISTING WHEELCHAIR/BICYCLE RAMP
	PROPOSED WHEELCHAIR/BICYCLE RAMP
	EXISTING BOLLARD OR POST

M.B.	MAIL BOX
#5	LOCATION OF TEST BORING WITH NUMBER
#5	LOCATION OF TEST PIT WITH NUMBER
3	BENCH MARK WITH NUMBER
	TRIANGULATION OR CONTROL POINT
	BREAK IN GRADE
	STATION EQUATION
2	REVISION WITH NUMBER
45.67	EXISTING SPOT ELEVATION (AND/OR FEATURE)
45.67	PROPOSED SPOT ELEVATION (AND/OR FEATURE)
	EXISTING BASE LINE OR CENTER LINE
BL	PROPOSED BASE LINE
CL	PROPOSED CENTER LINE
	STATE LINE
R.O.W.	RIGHT-OF-WAY LINE
	BUILDING RESTRICTION LINE
	LOT LINE
	EXISTING FENCE (Indicate Type)
	PROPOSED FENCE (Indicate Type)
	EXISTING GUARDRAIL - DOUBLE FACE
	PROPOSED GUARDRAIL - DOUBLE FACE
	EXISTING GUARDRAIL - SINGLE FACE
	PROPOSED GUARDRAIL - SINGLE FACE

DATE	APPR.	REFERENCE
REVISED		
ISSUED:		

RECOMMENDED: DEPUTY CHIEF ENGINEER

APPROVED: CHIEF TRANSPORTATION ENGINEER

STANDARD SYMBOLS

d. DISTRICT OF COLUMBIA
DEPARTMENT OF TRANSPORTATION

DWG. NO. GEN.02

p:\4035\dc standard drawings\final\UNCHANGED\gen-02.dgn
Friday, April 03, 2009 AT 12:13 PM

	PROPOSED 3 SECTION TRAFFIC SIGNAL
	PROPOSED 4 SECTION TRAFFIC SIGNAL
	PROPOSED 5 SECTION TRAFFIC SIGNAL
	EXISTING 3 SECTION TRAFFIC SIGNAL
	EXISTING 4 SECTION TRAFFIC SIGNAL
	EXISTING 5 SECTION TRAFFIC SIGNAL
	EXISTING LUMINAIRE AND SUPPORT ARM INDICATES DIRECTION OF LIGHT
	PROPOSED LUMINAIRE AND SUPPORT ARM INDICATES DIRECTION OF LIGHT
	REMOVE INDICATED TRAFFIC SIGNAL OR STREETLIGHT UNIT
	EXISTING PEDESTRIAN SIGNAL
	PROPOSED PEDESTRIAN SIGNAL
TC	EXISTING TRAFFIC SIGNAL CONTROLLER
TC	PROPOSED TRAFFIC SIGNAL CONTROLLER
TEC	EXISTING TRAFFIC SIGNAL COMMUNICATION CABINET
TEC	PROPOSED TRAFFIC SIGNAL COMMUNICATION CABINET
	EXISTING SL/TS CONDUIT - SL=STREETLIGHT, TS=TRAFFIC SIGNAL
# - 2"	PROPOSED 2" PVC CONDUIT
# - 4"	PROPOSED 4" PVC CONDUIT
# - 2" & #- 4"	PROPOSED 2" & 4" PVC CONDUITS
2 - 4"	PROPOSED 2-4" PVC CONDUITS
4 - 4"	PROPOSED 4-4" PVC CONDUITS
* P	PROPOSED LOCATION FOR PEPCO POWER CONNECTION
	EXISTING 6'x6'x6' ELECTRICAL MANHOLE
	PROPOSED 6'x6'x6' ELECTRICAL MANHOLE
	EXISTING 4'x4'x6' ELECTRICAL MANHOLE
	PROPOSED 4'x4'x6' ELECTRICAL MANHOLE
	EXISTING 4'x4'x4' ELECTRICAL MANHOLE
	PROPOSED 4'x4'x4' ELECTRICAL MANHOLE
	EXISTING 3'x3'x3' ELECTRICAL MANHOLE
	PROPOSED 3'x3'x3' ELECTRICAL MANHOLE
	EXISTING #4 STREETLIGHT POLE
	PROPOSED #14 STREETLIGHT POLE
	EXISTING #6 STREETLIGHT POLE
	PROPOSED #6 STREETLIGHT POLE
	EXISTING #8 STREETLIGHT POLE
	PROPOSED #8 STREETLIGHT POLE
	EXISTING TWIN 20 STREETLIGHT POLE
	PROPOSED TWIN 20 STREETLIGHT POLE
	EXISTING 5A STREETLIGHT POLE
	PROPOSED 5A STREETLIGHT POLE
	EXISTING PENDANT POLE
	PROPOSED PENDANT POLE
	EXISTING PEPCO WOOD POLE
	PROPOSED PEPCO WOOD POLE
	EXISTING DC WOOD POLE
	PROPOSED DC WOOD POLE
	EXISTING 20 FOOT TRAFFIC SIGNAL POLE
	PROPOSED 20 FOOT TRAFFIC SIGNAL POLE
TS	TRAFFIC SIGNAL(S) MOUNTED ON STREETLIGHT POLE

DATE	APPR.	REFERENCE
REVISED		
ISSUED:		

RECOMMENDED: DEPUTY CHIEF ENGINEER

APPROVED: CHIEF TRANSPORTATION ENGINEER

STANDARD SYMBOLS

d. DISTRICT OF COLUMBIA
DEPARTMENT OF TRANSPORTATION

DWG. NO. GEN.03

p:\4035\dc standard drawings\final\UNCHANGED\gen-03.dgn
Friday, April 03, 2009 AT 12:13 PM